

Exhibit B

SITE ACTIVITY PLAN : TIMBER HARVEST

RMU: **Elk River**
Sale ID: **2007-2-1**
Sale Name: **Park Road 24**
Total Sale Acres: **241**
Total Treatment Acres: **241**
FPA Notification #:

Plan Date: **02/22/2007**
Prepared by: **Jones, Dan**
Administered by: **Stone, Trevor**
Area Manager: **Jones, Dan**
Unit Manager: **Mattson, Katharine**
Logging Contractor:

Unit 1: 79 acres
Unit 2: 45.3 acres
Unit 3: 116.5 acres

Area Description (map attached)

Harvest unit boundaries (internal and perimeter): All harvest unit boundaries are marked as follows: Property boundaries are marked with 2 horizontal red marks and red ribbon. All other boundaries are marked with 2 horizontal orange marks and orange ribbon.

Access control comments: There is direct access from county road to Potlatch timber sale area.

Silvicultural Objective

Silvicultural objective: The silvicultural objective for this sale is to harvest the current mature stand and replace it with plantation.

Harvest Instructions

Harvest prescription: Clearcut

Harvest instructions: Remove all merchantable material. In mid-December 2006 a wind event caused blowdown primarily on Units 2 and 3. An estimated 100-25 mbf were affected in this event. Removal of all blowdown material is required to be completed on this sale by July 15th.

Value Added Products: A portion of western red cedar volume may be of pole quality.

Cutting specifications: Tonwood removal is optional. See Timber Sale Contract for full utilization and merchantability standards.

Danger Trees: Type III and IV trees must be felled as encountered during the operation. Type II trees that are likely to become Type III or IV within the next 18 months must be felled. (See Guide: Risk Assessment for Identifying Reserve Trees)

Roads, trails, and landings: Use existing trail system. No excavated trails will be allowed except by specific permission from Potlatch Representative. Temp spurs must also be pre-approved by Potlatch Representative. Construction and closure costs will be the responsibility of the purchaser.

Equipment requirements: With the exception of a small portion of Unit 3 that may potentially require short-line logging, this sale is suitable for ground skid systems. If a feller/buncher and whole-tree skid system is used, 50% of limb and top material must be left dispersed across the unit. Planned efforts to achieve this requirement will need to be identified within the Logging Plan.

Special Instructions

Public safety: Proper signing of access roads is required. Flagman required when felling adjacent to county road.

Stream / Riparian: Follow Forest Practice Act rules when operating near Class II Stream Protection Zones, Maintain an equipment exclusion zone of 30 feet from stream and retain sub-merchantable material within 50 feet of Class II streams.

Special sites: Minimize disturbance to old homestead site located in unit 3

Other uses of concern: Cistern and water pipe line located in Class II stream on western edge of unit 1. Cistern and water line are marked with pink ribbon. A 5 foot equipment exclusion on each side of the ribbon line will minimize potential damage to the system. Repair of any logging related damage to the water system will be the responsibility of the purchaser.

Erosion Control Instructions

Forest Practices Act erosion control requirements must be met. Other special requirements are listed below if applicable.

Skid trails and skidding Any skid trails constructed or used by Purchaser will be cross-ditched to Contract standards.

Roads, ditches, and culverts: Purchaser is responsible for cleaning ditch lines, culvert heads, and outlets, and pulling skid trail approaches. Dirt portions of designated sale roads will be bladed and shaped with rolling dips installed following completion of hauling.

Hazard Management Instructions

Slash disposal: No requirement for piling slash within the sale boundaries. Keep slash pile at least 30 feet from non-road sale boundaries.