

# Exhibit B

## SITE ACTIVITY PLAN : TIMBER HARVEST

RMU: **Pierce**  
Sale ID: **2007-3-1**  
Sale Name: **FLAT PATCH EAST**  
Total Sale Acres: **124**  
Total Treatment Acres: **124**  
FPA Notification #:

Plan Date: **02/19/2007**  
Prepared by: **Rayner, Don**  
Administered by: **Rayner, Don**  
Area Manager:  
Unit Manager: **McMillan, Rich**  
Logging Contractor:

Unit 1: 124 acres

### Area Description (map attached)

**Harvest unit boundaries (internal and perimeter):** The road is the sale boundary with the exception of a small piece on the north end. This part of the boundary is marked with orange ribbon and paint. See attached map for sale boundaries. Total harvest acres in unit is approximately 124.

**Access control comments:** Access controlled by guard rail gate.

### Silvicultural Objective

**Silvicultural objective:** To harvest all merchantable timber and replace the existing stand with a plantation of mixed species.

### Harvest Instructions

**Harvest prescription:** Clearcut

**Harvest instructions:** Remove all merchantable timber from the stand.

**Cutting specifications:** Remove all merchantable timber. Ton wood and pulp removal is optional. See contract for utilization specifications.

**Danger Trees:** Type III and IV trees must be felled as encountered during the operation. Type II trees that are likely to become Type III or IV within the next 18 months must be felled. (See Guide: Risk Assessment for Identifying Reserve Trees)

**Roads, trails, and landings:** The contractor is responsible for cleaning the ditch lines, culvert heads and outlets, and pulling the skid trail approaches. The portion of the haul road that has a dirt surface will be bladed and shaped with rolling dips installed following completion of hauling. Temporary Spurs, if needed, will be preapproved by Potlatch Rep. Construction and closure costs will be the responsibility of the purchaser.

**Equipment requirements:** This timber sale is 100% ground skid. If feller/buncher and whole tree skid system is used, 50% of limb and top material must be left within the unit. In this case, planned efforts to achieve this requirement will be identified within the logging plan. Minimize number of needed skid trails. No excavated trails will be allowed except by specific permission from Potlatch Representative.

## Special Instructions

- Public safety:** The use of proper warning signs is required at both access points.
- Stream / Riparian:** Keep equipment 50 feet outside of class II streams at all times. Retain all sub-merchantable and non-merchantable timber within the SPZ to the extent reasonable. Sale administrator can approve the equipment entry into the 30 foot regulatory SPZ.

## Erosion Control Instructions

Forest Practices Act erosion control requirements must be met. Other special requirements are listed below if applicable.

- Skid trails and skidding** Any skid trails constructed or used by contractor will be crossditched in accordance with Potlatch EMS standards.

## Hazard Management Instructions

- Slash disposal:** Contractor is responsible for keeping all logging slash inside stand boundaries. Any logging slash placed in road or outside of unit boundaries will be moved inside the road or unit boundaries by the contractor at his own expense. All slash concentrations will kept dirt-free. Potlatch is responsible for slash hazard management after sale is closed.